

STATE OF KANSAS
STATE CORPORATION COMMISSION
2078 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21403-000

LEASE NAME Richards Family Trust

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 3 TWP. 23 RGE. 16W (E) or (W)

COUNTY Pawnee

Date Well Completed

Plugging Commenced 11-3-97

Plugging Completed 11-6-97

OPERATOR Wayne E. Walcher

ADDRESS 701 Bitting Bldg. Wichita, Ks. 67202

PHONE (316) 267-1611 OPERATORS LICENSE NO. 5403

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4082'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	309'	None
				5-1/2"	4080'	2218'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3750' and 5 sacks cement. Shot @3000', 2800', 2400', 2218', pulled up to 1000', pumped 8 sks. gel. 50 cement w/1/4# flo-seal per sack, pulled to 600', pumped 50 sks. cement, pulled to 320', pumped 50 sks. cement, pulled to 40' and pumped 45 sacks to top off. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Wayne E. Walcher

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1997

Irene Herzberg
Notary Public

My Commission Expires:

