


15445-00075-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 3 Twp. 23 Rge. (E) 16 (W)

Location as "NE/CNW/SE/SW" or footage from lines SE SE NW
Lease Owner Messman-Rinehart Oil Company
Lease Name Aldrich Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 2, 1953 19
Application for plugging filed February 25, 1957 19
Application for plugging approved February 25, 1957 19
Plugging commenced March 7, 1957 19
Plugging completed March 9, 1957 19
Reason for abandonment of well or producing formation Reservoir depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production February 15, 1957 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege, Box 283, Hoisington, Kansas
Producing formation Lansing Depth to top 3705 Bottom 3716 Total Depth of Well 4096 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	217'	None
				5 1/2"	4090'	2994'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock to 4085', dumped 5 sax cement @ 4085 w/dump bailer. Top of cement 4050'. Pumped in 25 sax Gel-Mud & 80 sax cement by Globe Cementing Co. to plug well.

3-15-57
STATE CORPORATION COMMISSION
MAR 15 1957
CONSERVATION DIVISION

Name of Plugging Contractor Miller Casing Pulling Co.
Address P. O. Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) *J. A. Gilliland*
518 Petroleum Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of March, 1957

Claine M. Malone
Notary Public.

My commission expires September 5, 1960

PLUGGING
FILE SEC 3 T. 23 R. 16 W
BOOK PAGE 143 LINE 30

ALDRICH #1

15-145-00075-0000

WELL RECORD

Location: SE SE NW 3-23-16W
Pawnee County, Kansas

Commenced: October 5, 1953

Completed: November 2, 1953

Operator: Graham-Messman-Rinehart Oil Company
1005 E. 2nd. Street, Wichita, Kansas

Elevation: 2048 K.B.

Contractor: Graham-Messman-Rinehart Drilling Co.
1005 E. 2nd. Street, Wichita, Kansas

Production: Oilwell

Casing Record: 5 5/8" @ 217' w/158 sx. cem.
5 1/2" @ 4091 w/120 sx. cem.

LOG

Sand	180	Conglomerate	4047
Shale	217	Simpson Shale	4065
Shale	345	Shale	4084
Sand	380	Arbuckle	4092
Shale & Red Bed	500		4095 T.D.
Sand	535		
Shale	1035		
Shale	1117		
Anhydrite	1152		
Shale-Shells	1350		
Shale & Red Bed	1800		
Lime & Shale	1850		
Shale & Lime	2020		
Shale Lime	2164		
Lime & Shale	2285		
Lime & Shale	2380		
Lime Shale	2445		
Lime & Shale	2595		
Lime & Shale	2735		
Lime Shale	2873		
Lime & Shale	3000		
Lime & Shale	3170		
Lime Shale	3299		
Lime & Shale	3395		
Shale & Lime	3460		
Lime Shale	3535		
Shale	3604		
Lime	3623		
Lime	3650		
Lime	3695		
Lime	3713		
Lime	3742		
Lime	3804		
Lime	3823		
Lime	3865		

TOPS


Anhydrite - 1152 (+ 396)
 Lansing - 3611 (-1563)
 Base Kansas City - 3349 (-1801)
 Conglomerate - 3956 (-1908)
 Simpson - 4047 (-1999)
 Arbuckle - (4085 (-2037)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM - MESSMAN - RINEHART DRILLING COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 27th day of October, 1953.



RECEIVED
 STATE COMMISSION
 MAR 1 1957
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 3 T. 23 R. 16W
 BOOK PAGE 143 LINE 30

GMR
File Copy