

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-20521-0000

LEASE NAME Salmans

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC 26 TWP. 23 SRGE. 16 (E) or (W)

COUNTY Pawnee

Date Well Completed 5-25-78

Plugging Commenced 7-11-88

Plugging Completed 7-22-88

LEASE OPERATOR Continental Energy

ADDRESS 906 S. Highway, 83 Frontage Road
Garden City, Kansas 67846

PHONE (316) 275-9799 OPERATORS LICENSE NO. 5317

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	388'	none
				5-1/2"	4249'	2963'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 200# hulls and 30 sacks cement to 3300'. Shot pipe @3257', 2963', pulled a total of 78 joints of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 150 cement, 60/40 pos., 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 88

Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG - 9 1988

CONSERVATION DIVISION
Wichita, Kansas
Commission Expires:

