


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rice County, Sec. 8 Twp. 21a Rge. 6W (E) (W)  
Location as "NE/CNW/SW" or footage from lines. C E/2 SE SE  
Lease Owner Northridge Oil Company  
Lease Name Walsten Well No. I-F  
Office Address Box 18271 # Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 9-24 19 70  
Application for plugging filed 10-30 19 71  
Application for plugging approved 11-1 19 71  
Plugging commenced 11-15 19 71  
Plugging completed 11-18 19 71  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3523' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,433'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3523' to 3500'. Dumped 5 ax of cement. Mudded hole to 210'. Made 10' of rack bridge. Dumped 35 ax of cement. Mudded hole to 40'. Made 10' of rack bridge. Dumped 10 ax of cement, filling to the bottom of the cellar.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 22 1971

CONSERVATION DIVISION  
Wichita, Kansas

11-22-71

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 71

My commission expires January 5, 1974

Judy Lamb  
Notary Public.

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SA... BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

15.159.20326.0000

COMPANY **COMMERCIAL OIL, INC.**

SEC. 8 -213 .6W  
 LOC. Approx. C E/2 SE SE

FARM **Walsten**

NO. 1 "P"

TOTAL DEPTH **3,523'**

COMM. **9-17-70**

COMP. **9-24-70**

COUNTY **Rice**

KANSAS

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED

CASINO

20  
15  
12  
13

10  
8-5/8" 168' w/185 bxs. cement  
6  
5-1/2" 3,517' w/50 bxs. cement

ELEVATION **1693 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Beds	265
Shale	1060
Shale and Lime	1295
Lime and Shale	1552
Shale and Lime	2485
Lime	2675
Lime and Shale	2985
Lime	3217
Lime and Shale	3295
Lime	3475
Lime and Shale	3523

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 1 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.


Dean Britting  
 Dean Britting

STATE OF KANSAS

COUNTY OF SEDGWICK

SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 28th. day of September, 1970.



Elsie Willison  
 Elsie Willison - Notary Public

Commission Expires:

June 30, 1974