


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rice County. Sec. 8 Twp. 21 Rge. 6 (#) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NW  
Lease Owner Henry Bennett  
Lease Name Walstien Well No. 2  
Office Address Union National Bank Bldg.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed Jul August 7 19  
Application for plugging filed August 7 19  
Application for plugging approved " 19  
Plugging commenced " 19  
Plugging completed " 19  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3543 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	143'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full heavy mud to 143 feet.  
drove wooden plug to 143 feet and dumped in  
15 sacks cement. finished filling hole  
full heavy mud to withing 35 feet of cellar  
and dumped in 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Henry Bennett  
Address Union National Bank Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *HC Bennett*  
P. O. Box 31, Augusta, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of August 1951

My commission expires Jan. 31, 1953

RECEIVED Notary Public.  
STATE CORPORATION COMMISSION

23-3278-s 4-50-10M

AUG 13 1951

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILED SEC 8 T 21 R 6 W  
BOOK PAGE 10 LINE 24

COMPANY:

Henry Bennett

CONTRACTOR:

Mallard Drilling Company

FARM:

Walstien #2

LOCATION:

NE NW NW Sec. 8-21-6W  
Rice County, Kansas

COMMENCED:

July 29, 1951--rotary

COMPLETED:

August 7, 1951--rotary

0	to	143	Surface sand
143	to	365	Red bed and shale
365	to	700	Shale and shells
700	to	1100	Shale and shells
1100	to	1320	Shale and lime
1320	to	1465	Shale and lime
1465	to	1630	Sand and lime
1630	to	1735	Sandy lime
1735	to	2015	Shale and lime
2015	to	2490	Shale and lime
2490	to	2570	Lime and shale
2570	to	2805	Lime
2805	to	3000	Lime and shale
3000	to	3340	Lime
3340	to	3430	Lime and shale
3430	to	3481	Shale and lime
3481	to	3513	Conglomerate
3513	to	3518	Mississippi
3518	to	3543	Mississippi
		3543	T.D.

Set 143 feet of 8 5/8" surface pipe. Cemented with 120 sacks cement.

TOPS:--3513 to 3543 --Mississippi

Measurements taken from derrick floor.

DRY, ABANDONED AND PLUGGED

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Walstien #2, NE NW NW, Sec. 8-21-6W, Rice County, Kansas, as reflected by files of the Mallard Drilling Company.

*C. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 17th day of August 1951.

*[Signature]*

Subscribed and sworn to  
My commission expires 1/7/4/59

PLUGGING  
NE NW NW Sec. 8-21-6W  
BOOK PAGE 10, LINE 24

RECEIVED  
STATE CORPORATION DIVISION  
AUG 13 1951  
CONSERVATION DIVISION  
Wichita, Kansas