

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-009-03334-00-00

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

API NUMBER _____
LEASE NAME Penka #2 "A"
WELL NUMBER _____
SPOT LOCATION SE SE SE
SEC 22 TWP 16s RGE 12w (E) OR (W)
COUNTY Barton
DATE WELL COMPLETED _____
PLUGGING COMMENCED 8/25/83
PLUGGING COMPLETED 9/7/83

LEASE OPERATOR Southern States Oil Co.
ADDRESS P.O. Box 1365, Great Bend, Ks. 67530
PHONE #() _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita

IS ACC-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3388 1/2'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	310'	none
				5 1/2"	3388 1/2'	2176'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged off bottom with 5 bags cement, sanded to 3057', 50' above perms, & 5 bags cement. Shot casing at 2500', 2400', 2300', & 2200'. Pulled total of 65 joints.. Plugged well with 4 hulls, 12 gel, 65 cement, 3 gel, 1 hull, plug, & 100 sacks 50/50 poz 8% gel 3% c.c. Plugging complete.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050
ADDRESS Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso
(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 8th DAY OF September, 1983

Irene Hoover
NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-4
REVISED 06-83

SEP 12 1983

9-12-83

CONSERVATION DIVISION
Wichita, Kansas

15-009-03334-00-00

THE VICKERS PETROLEUM CO., INC.

Penka "A" Well #2 ✓
SE SE SE Sec. 22-16S-12W
Barton County, Kansas

Casing Record:
8-5/8" @ 310' w/160 sx
5-1/2" @ 3377 1/2' w/75 sx

Commenced: February 15, 1950
Completed: March 4, 1950

Elevation: 1922 R.B.
Potential: 718 BOPD

LOG

Shale & Shells	0-180
Shale, Shells & Sand	180-470
Sand & Shale	470-550
Red Bed & Shale	550-809
Anhydrite	809-831
Shale & Shells	831-1250
Salt & Shale	1250-1290
Salt, Shale, & Shells	1290-1465
Shale & Lime	1465-1570
Broken Lime	1570-1685
Broken Lime & Sand	1685-1875
Lime & Sand	1875-1910
Broken Lime	1910-2050
Lime	2050-2160
Lime & Shale	2160-2610
Lime	2610-2900
Lime & Shale	2900-3023
Shale & Sand	3023-30855
Lime & Shale	3085-3348
Shale & Lime	3348-3369
Shale, Sand & Chert	3369-3377
Arbuckle	3377-3380 RTD

Drilled Deeper 3380-3385 1/2
 No fluid after 14 hrs.
 Drilled Deeper 3385 1/2-3388 1/2 T.D.
 Made 1 BOPD
 Acidized w/1000 gal; swabbed hole to bottom,
 Set 25 min. Swab 11.69 bbls. fluid.
 Swab all acid water plus 10 bbls. extra water
 and 20 bbl. oil
 Fill up 2380' fluid in 14 hrs. 2 bailers water
 Swab 21 BOPD, no water

Tops:	
Heebner 2997	2997
Brown Lansing	3085
White Lansing	3104
Conglomerate	3369
Arbuckle	3377
(Pay zone)	3386- <i>Regan ????</i>

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By *H.C. Davis*

Sworn and subscribed to before me
this 6th day of March, 1950.

Allen P. Denton
Notary Public

My commission expires August 13, 1953.

RECEIVED
STATE CORPORATION COMMISSION

JUL 07 1953

CONSERVATION DIVISION
Wichita, Kansas