


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 22 Twp. 16 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE NE SE

Lease Owner Tenneco Oil Company
Lease Name John Riemann B Well No. 3
Office Address 139 Ciudad Bldg., Oklahoma City, Okla.
Character of Well (Completed as Oil, Gas or Dry Hole) 73112
oil



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced March 20 1978
Plugging completed March 31 1978
Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3370'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	236'	8 5/8"	236'	none
			3368'	5 1/2"	3368'	1999.70

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3015' and dumped 5 sacks of cement.

Halliburton Services plugged well pumping in 5 sacks of hulls, 25 sacks of gel and 100 sacks of cement.

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

APR 07 1978
4-7-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.
Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner-or-operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas 67526
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1978

JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

My commission expires

Jenny Kasselman
Notary Public.

15-009-03337-0000


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETROLEUM CORPORATION
Farm - Riemann "B" No. 3

SEC. 22 T. 16 R. 12W
NE NE SE

Total Depth. 3370
Comm. 5-21-49 Comp. 7-6-49
Shot or Treated. Acid.
Contractor. L-S-T Drilling
Issued. 8-6-49

County. Barton
KANSAS



Elevation. _____

Production. Phys. 112 bbls.

Figures Indicate Bottom of Formations.

surface clay, sand, gravel	70
shale, shells	155
shale blue	236
sand	250
shale	475
sand	495
shale, iron	510
sand, iron	555
redbed, shale	650
shale, shells	815
anhydrite	840
shale, shells	940
salt, shells	1130
salt	1225
shale, shells	1520
lime, shale	1950
shale, lime, gyp	2040
lime	2070
lime, shale	2090
lime, shale	2165
lime, shale	2300
shale, lime shells	2460
lime, shale	2825
lime	2963
lime, shale	3110
lime	3370
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1978

CONSERVATION DIVISION
Wichita, Kansas

Tops:

Brown Lansing	3092
Lansing	3108
Arbuckle	3368

DP. CO to RTD., 8 BOPH,
500 acid., Swb. 1000' OPH
1000' OB, FU 2070' oil overnite.