

15-009-03339-00-01


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County, Sec. 22 Twp. 16 Rge. 12 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NW NW SE

Lease Owner Tenneco Oil Company  
Lease Name John Riemann A Well No. 1  
Office Address 139 Ciudad Bldg., Oklahoma City, Okla.  
Character of Well (Completed as Oil, Gas or Dry Hole) 73112  
oil EOR



Locate well correctly on above  
Section Plat

Date Well completed Dec. 8 1977  
Application for plugging filed Sept. 23 1977  
Application for plugging approved Sept. 27 1977  
Plugging commenced Nov. 7 1977  
Plugging completed Nov. 14 1977  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3371'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			272'	8 5/8"	272'	none
			3357'	5 1/2"	3357'	613.20

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Sanded back to 3150' and dumped 5 sacks of cement.

Halliburton Services plugged well pumping in 3 sacks of hulls, 10 sacks of  
gel and 100 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1977 11-16-77

(If additional description is necessary use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.  
Box 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (~~owner or operator~~)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 77

My commission expires \_\_\_\_\_

JENNY KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COMM. EXP. JULY 16, 1978


Jenny Kasselmann  
Notary Public.

C. J. BAY,  
Riemann No. 1.

S. 22 T. 16 R. 12 W.  
NW 6E

Total Depth. 3371 P.B. 3362  
 @own. 11-10-41 Comp. 12-8-41  
 Shot or Treated. 4 qts 3360-62 8 qts 3361-70  
 Contractor.  
 Issued. 2-14-42

County Barton.



CASINO.

85/8" 272' 5 1/4" 3367'

Elevation.

Production. Pot. 252 B.

Figures Indicate Bottom of Formations.

surface clay	17
sand	28
shale shells	275
shale shells	428
shale and sand	507
shale and shells	585
shale red	660
shale shells	836
anhydrite	864
shale	875
shale lime shells	1030
shale and shells	1246
shale and salt	1492
lime&shale strks	1602
shale and lime	1754
shy lime and shale streaks	1820
lime	1965
lime and shale	2159
shale and lime strks	2310
shale and lime	2380
shale	2544
lime and shale	2755
lime brown	2794
lime	3045
lime and shale	3050
lime	3355
lime	3361
sand	3367
shy dolomite	3371
Total Depth. P.B. 3362	

RECEIVED  
 STATE COMMISSIONER OF GEOL. & MINES  
 SEP 21 1977  
 CONSERVATION DIVISION  
 Topeka, Kansas

Top Lansing Kansas City 3085  
 Gorham 3354 1/2