

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-009-06554-00-00
WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

Barton County, Sec. 22 Twp. 16S Rge. (E) 12 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines G NW/4 SE/4 SE/4
Lease Owner C. U. Bay
Lease Name Penka A Well No. One
Office Address 321 Union Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 7, 1942 19. 42
Application for plugging filed January 7 19. 42
Application for plugging approved January 10 19. 42
Plugging commenced January 7 19. 42
Plugging completed January 7 19. 42
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation Depth to top Bottom Total Depth of Well 3419 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8" OD	275'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud from 3419' to 286'
Permanent bridge placed at 286' and cemented with 10 sacks
Mud from 286' to 35'
Cement 35' to 5'
Mud 5' to Top

22 16:1 EW
21 NW 8-1

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to H. I. Craig, Production Superintendent
Address The Bay Petroleum Corporation
321 Union Nat'l Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. P. Hemphill (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. P. Hemphill* 1-15-42
321 Union Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of January, 1942

My commission expires June 5, 1944

Virginia Vermillion
Notary Public.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

C.U.BAY
Penka "A" No. 1.

SEC. 22 T. 16 R. 12 W.
NW SE SE

Total Depth. 3419
Comm. 12-20-41 Comp. 1-7-42
Shot or Treated.
Contractor.
Issued. 1-17-42

County Barton.



CASING.

8 5/8" 286 Cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

soil	15
shale sand and shells	220
shale and shells	284
shale shells and sand	472
shells	543
shale red and shells	589
shale and shells	779
anhydrite	825
shale and lime	863
shale and shells	1235
shale and lime	1247
shale and salt	1441
salt	1485
anhydrite shale	1550
salt and shells	1630
shaly lime	1664
shale and lime	1814
shaly lime	1833
lime brown rough	1881
lime and shale	1955
lime	1996
lime and shale	2060
lime	2136
lime and shale	2556
lime and shale strks	2600
shale	2681
shale and lime	2773
lime	3117
lime and shale	3146
lime	3148
lime and chert	3172
lime	3389
chert and lime	3410
lime	3419

Total Depth.

slight show oil 3030-35
Fair to poor porosity, very light stain 3194-3213
good porosity, no stain 3205-20
Fair porosity 3282-93

Tops -

Topeka	2655
Hebner	3040
Lansing Brown	3095
Lansing White	3112
Conglomerate	3371
Arbuckle	3382

