

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-075-20109-00-00

LEASE NAME Levens

WELL NUMBER 1-10

1980 Ft. from N. Section Line

1980 Ft. from E. Section Line

SEC. 10 TWP. 21S RGE. 40W (E) or (W)

COUNTY Hamilton

Date Well Completed 04/27/76

Plugging Commenced 01/23/02

Plugging Completed 01/23/02

RECEIVED  
FEB 22 2002  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE/(405) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01/15/02 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Towanda Depth to Top 2834 Bottom 2842 T.D. 2988'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	320'	
				4-1/2"	2970'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each section.

Pump 500# hulls, follow up w/130 sx cement down 4-1/2", SI w/1700#, tied onto 8-5/8", pump 60 sx cement; SI w/300# Kevin Strube state representative

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF OK COUNTY OF OK, ss.

Randy Gasaway (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Randy Gasaway

(Address) P. O. Box 18496, Okla. City, OK

73154-0496

SUBSCRIBED AND SWORN TO before me this 20 day of February, 2002

Jan E. Fair Notary Public

My Commission Expires: My Commission Expires Jul. 22, 2004.



# ALLIED CEMENTING CO., INC.

09206

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Ogale

DATE <u>1-23-02</u>	SEC. <u>10</u>	TWP. <u>21s</u>	RANGE <u>40W</u>	CALLED OUT	ON LOCATION <u>9:20 AM</u>	JOB START <u>9:30</u>	JOB FINISH <u>10:10</u>
LEVEN'S # LEASE	WELL # <u>1-10</u>	LOCATION <u>Syracuse 17N 3E 2N E/3</u>			COUNTY <u>Hamilton</u>	STATE <u>Ks</u>	

OLD OR NEW (Circle one)

CONTRACTOR \_\_\_\_\_ OWNER Same

TYPE OF JOB O.H.P.

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH 2970

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 1700 MINIMUM 90

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG \_\_\_\_\_

PERFS. 2934-2842

DISPLACEMENT \_\_\_\_\_

CEMENT

AMOUNT ORDERED 300 sks 60/40 + 69.9-e/

used 190 sks 60/40 + 69.9-e/

500 # C.S. Halls

COMMON	<u>114 sks</u>	@	<u>7.85</u>	<u>894.90</u>
POZMIX	<u>76 sks</u>	@	<u>3.55</u>	<u>269.80</u>
GEL.	<u>10 sks</u>	@	<u>10.00</u>	<u>100.00</u>
CHLORIDE		@		
C.S. Halls	<u>500 sks</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>320 sk</u>	@	<u>1.10</u>	<u>352.00</u>
MILEAGE	<u>48/51 mi</u>			<u>896.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Jerry - Max Full

# 300 HELPER Wayne - J. Hall

BULK TRUCK

# 357 DRIVER Jim

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED

FEB 22 2002

TOTAL 2602.70

REMARKS:

KCC WICHITA SERVICE

Pump Down 5 1/2 Csg 500 # C.S. Halls + 170 sks  
Cmt Pressure To 1700 Shut in @ 900  
Hookup To ANN Mix 60 sk cmt Pressure  
To 300 P.S.I. Shut in @ 0 Hole in Surface  
Csg

DEPTH OF JOB 2842

PUMP TRUCK CHARGE \_\_\_\_\_ 225.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE \_\_\_\_\_ @ \_\_\_\_\_

PLUG \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 225.00

CHARGE TO: Chesapeake Operating

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE: Dennis D. [Signature]

PRINTED NAME