

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-01450-00-01  
Spot: N2N2NW Sec/Twnshp/Rge: 16-16S-12W  
4950 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: KULTGEN Well Number: 3  
County: BARTON Total Vertical Depth: 3352 feet

Operator License No.: 5230  
Op Name: PETROLEUM ENERGY, INC.  
Address: 224 E. DOUGLAS - 350 KRESS ENERGY  
WICHITA, KS 67202

Production Casing Size: 6.625 feet: 3320 w/150 sxs cmt  
Surface Casing Size: 15 feet: 349

Well Type: SWD UIC Docket No: D13880.0 Date/Time to Plug: 05/27/2003 9:30 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 550 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/27/2003 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1250' and 820'.  
Swaged onto 6 5/8" - mixed and pumped 250 sxs cement with 500# hulls.  
Displaced to 300' - perforated casing at 300'.  
Swaged onto 6 5/8" and circulated up surface with 250 sxs cement.  
Hole full of cement.

THIS IS A KCC FEE FUND PLUGGING.


RECEIVED  
JUN 04 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

→→→ HAYS OFFICE

DARBY PETR

#3 KURTGEN

16-16-12W  
G NL NW

Contr.

BARTON County

E 1910

Comm. 6-26-36

Comp. 8-12-36

IP

929 BOPD

Tops	Depth	Datum
ANH	817	
FT R	1745	
TOP	2703	
LANS	3072	
BSL SD	3343	
TD	3352	

Casing  
6" 3320

2000' OIH/8 hr


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

05/29/03 THU 09:34 FAX 3163376247