

7-25

To: 6 061560  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,998 -00-00  
NE, SEC. 17, T 16 S, R 12 W/E  
3630 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7062

Lease Name Kultgen A Well # 6

Operator: Keener Oil Co.

County Barton 111.15

Name & Address 320 S. Boston

Well Total Depth 3420 feet

Tulsa, Ok. 74103

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 808

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 10:00AM Day: 25 Month: July Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pdling Inc. (phone)

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1988

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Gilbert Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:30PM Day: 25 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 808' w/365 sks. 4 1/2" set at 3416' w/175 sks.

Top perf at 3342'. Plugged bottom w/sand and 5 sks cement to 3300'. Shot pipe 6 times and recovered 2500'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/600 Psi.

Remarks: by Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 9-20-88

INV. NO. 22298

Signed Gilbert G. Scheck (TECHNICIAN)

Gilbert G. Scheck