

TO: 4041331
STATE CORPORATION COMMISSION

12-29

21458-00-000KCC af3
API NUMBER 15-145-21458
E/2 E/2 SE SEC. 3, T 23 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME RICHARDS WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PAWNEE 133.25

OPERATOR LICENSE # 8061 WELL TOTAL DEPTH 4100' FEET

OPERATOR: OIL PRODUCERS INC. OF KANSAS PRODUCTION CSG: SIZE 4 1/2" @ 4099' WITH 115 SX

NAME AND PO BOX 8647 2400 N WOODLAWN #115 SURFACE CASING: SIZE 8 5/8" @ 298' WITH 210 SX

ADDRESS WICHITA, KS ⁶⁷78208-8674

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR D.S. & W WELL SERVICING, INC LICENSE NUMBER 6901

ADDRESS PO BOX 231, CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 29 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) D.S. & W WELL SERVICING, INC (PHONE) 316-587-3361

WERE: PERFS AT 3996-4002 & 4014-4022

1ST PLUG SANDED BACK TO 3940' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU DUMP BAILER.

2ND PLUG PUMPED DOWN 8 5/8" WITH 300# HULLS- 10 SX GEL-50 SX CEMENT-10 SX GEL-100# HULLS-

8 5/8" WIPER PLUG & 125 SX CEMENT. MAXIMUM PSI =500#. SHUT IN AT 350#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:45 PM DAY: 29 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 3940' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU DUMP BAILER.

2ND PLUG PUMPED DOWN 8 5/8" WITH 300# HULLS-10 SX GEL-50 SX CEMENT-10 SX GEL-100# HULLS-

8 5/8" WIPER PLUG & 125 SX CEMENT. MAXIMUM PSI PRESSURE AT 500#. SHUT IN AT 350#.

STATE CORPORATION COMMISSION

JAN - 6 1999 1-6-99

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. 2297' OF 4 1/2" CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

1-12-99

60521