

To: 1.052188
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 145-21,403-0000
150' E OF
NE NE SW, SEC. 3, T 23 S, R 16 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License # 5403

Operator: Wayne E. Walcher
Name & Address: 701 Bitting Bldg.
Wichita, KS 67202

2310 feet from S section line

2820 feet from E section line

Lease Name: Richards Family Trust
Well # 1

County: Pawnee 132.67

Well Total Depth: 4082 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Mike's Testing & Salvage Inc. License Number 31529

Address: P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 6 Month: 11 Year: 1997

Plugging proposal received from: James Ray

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

was: 5 1/2" at 4080' with 150 sx cement, PBSD 4056', Perfs at 3623-28, 3711-14'

1st plug sand back to 3570' and dump .5 sx cement on top of sand through bailer,

2nd plug at 1000' with 80 sx cement, 3rd plug at 600' with 50 sx cement,

4th plug at 320' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by: Mike Maier
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 6 Month: 11 Year: 1997

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3740', 2nd plug sanded back to 3575' and dumped

5 sx cement on top of sand through bailer,

Spotted plugs through casing:

3rd plug at 1000' with 8 sx gel, 50 sx cement and 2 sx gel,

4th plug at 600' with 50 sx cement, 11-13-97

5th plug at 330' with 50 sx cement,

6th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2280' of 5 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE: 11-17-97

NO. 49516 Signed: Richard W. Lucy (TECHNICIAN)