

1 030287

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,404

PO

C N/2 SW SW, SEC. 22, T 23 S, R 16 W/E

660 feet N SE Corner of ~~XXX~~ section line

4950 feet W SE Corner of ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Gingrich Well # 1

Operator: Thornton E. Anderson

County Pawnee

Name & Address 840 1st National Bank Building

Well Total Depth 4061 131.98 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 26 Month: September Year: 19 84

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4058' Perfs at 2214-16'

Squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Alenort
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:45 pm Day: 26 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4058' Perfs at 2214-16'

Squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 105 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 09 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc. Recovered 1935' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (XXXXX/) observe this plugging.

Signed Steve Alenort
(TECHNICIAN)

DATE 10-11-84

INV. NO. 4222