

7-22-88 15-145-20521-0000

1 120115

API NUMBER 15 Drill Completion Date 5/25/78

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SE, SEC. 26, T 23 S, R 16 W/X
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317
Operator: Continental Energy
Name & Address: 906 S. Highway 83
Frontage Road
Garden City, KS 67846

Lease Name Salmans Well # 1
County Pawnee 138.13
Well Total Depth 4250 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 22 Month: 7 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4249' Perfs at 4110-26'

1st plug pump 2 sx hulls and 30 sx common cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p. Day: 22 Month: 7 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 400 lbs. hulls, 30 sx cement displaced to 4000',

2nd plug pumped in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pressure on 8 5/8" - pumping 0-500 psi and shut in 200. psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2963' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

DATE 8-4-88

Signed [Signature] (TECHNICIAN)

INV. NO. 21744