

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20533-00-00
Spot: NWSESE Sec/Twnshp/Rge: 17-21S-40W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease/Unit Name: GRILLIOT Well Number: 2-17
County: HAMILTON Total Vertical Depth: 2815 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: 8.625 325 WITH 190 SX CMT
Surface Casing: Size 8.625 feet: 325 WITH 190 SX CMT
Production: Size 4.5 feet: 2814 WITH 725 SX CMT
Liner: Size feet: 891.49

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/21/2002 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP DOWN 4 1/2" 400# HULLS & 130 SX CMT. PRESSURE TEST. PUMP DOWN ANNULUS 20 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/21/2002 10:00 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2814'. PERFS AT 2760-70'. PUMPED DOWN 4 1/2" CASING 400# HULLS & 130 SX CMT. MAXIMUM PRESSURE 1300#. SHUT IN AT 1000#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 20 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

RECEIVED
MAR 29 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

INVOICED MAR 26 2002

DATE March 29-02

INV. NO. 200206 1583

For: 1/3