

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20109-00-00  
Spot: CSWNE Sec/Twnshp/Rge: 10-21S-40W  
1980 feet from N Section Line, 1980 feet from E Section Line  
Lease/Unit Name: LEVENS Well Number: 1  
County: HAMILTON Total Vertical Depth: 2988 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: \$97.11  
Surface Casing: Size 8.625 feet: 320 WITH 250 SX CMT  
Production: Size 5.5 feet: 2970 WITH 550 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/23/2002 9:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 5 SX HULLS FOR PLUG, 150 SX 60/40 POZ MIX W/6% GEL. PRESSURE UP ON BACK-SIDE (8-5/8" X 4-1/2") & PUMP 50 SX DOWN ANNULUS IF NEEDED.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/23/2002 10:15 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2910'. PERFS AT 2834-42'. PUMPED DOWN 5 1/2" WITH 500# HULLS & 130 SX CMT. MAXIMUM PRESSURE 1700#. SHUT IN AT 800#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 60 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN AT 0#. HAD HOLE AT SURFACE. ANNULUS STAYED FULL.

1-31-02

RECEIVED

JAN 31 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D. Strube  
(TECHNICIAN)

INVOICED

JAN 29 2002

DATE Feb 1-02

INV. NO. 2002061326

Form OP-43