

10-17

4-010300

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15 009-03331-00-00

S2 SW NE /4 SEC. 22, 16 S, 12 W
~~4290~~ 2970 ¹⁷ feet from S section line
~~4620~~ 660 ¹⁰ feet from W section line
#10

Operator license# 7323Lease: Morgan 'B' Well # 1Operator: Hazen OilCounty: Barton 108.06

Address: 200 W. 10th Street
Ellinwood, Kansas 67526

Well total depth 3325 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 Inch @ 285 feet

Aband. oil well ☒ Gas well ☐ Input well ☐ SWD ☐ D & A ☐Plugging contractor: Allied Cementing License# -Address: Russell, Kansas 67665Company to plug at: Hour: 11:00 A.M. Day: 17 Month: October Year: 1997Plugging proposal received from: KentCompany: D.S. & W. Well Service Phone: -Were: Same as below.

10-22-97

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[☐], Part[☒], None[☐]

Completed: Hour: 1:30 P.M., Day: 17, Month: October, Year: 1997

Actual plugging report: Shot at 1440' and 875'. Well has been squeezed to near surface.
Tried to pump into, would not take fluid at P.S.I. 1000#. Ran tubing to 1500' and circulated
with 110 sxs 60/40 pozmix - 10% gel with 500# hulls. Tied onto backside and pumped 50 sxs
with 100# hulls. No problems. Cement came to surface 10' from well.
pressure

Remarks: Well Flowing.

Condition of casing(in hole): GOOD ☐ BAD ☐ Anhy.plug: YES ☒ NO ☐
Bottom plug(in place): YES ☐ CALC ☐ NO ☐ Dakota plug: YES ☒ NO ☐
Plugged through TUBING ☒ CASING ☐ Elevation: ☐ GL

I did[☒] / did not[☐] observe the plugging.

Corn Morris
(agent)

Form CP-2/3

INVOICED

DATE OCT 27 1997INV. NO. 49336

10-17