

6070331

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-23,896-00-00
120' W SE-SE-SE, SEC. 22, T 16 S, R 12

330 feet from S section line

450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4191

Lease Name BILL REIF Well #A #1

Operator Name: BETA ENERGY, INC

County BARTON 110.24

Address P.O. BOX 42

Well Total Depth 3392 feet

GREAT BEND, KANSAS

Conductor Pipe: Size 0 feet

67530

Surface Casing: Size 8 5/8 feet 398

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated TAG # 1892

Plugging Contractor WILLIAMSON DRILLING INC License Number 4087

Address GREAT BEND, KANSAS

Company to plug at: Hour: 3:00 PM Day: 10th Month: MARCH Year: 1985

Plugging proposal received from TERRY WILLIAMSON

(company name) WILLIAMSON DRILLING INC (phone) 316-792-4178

were: 8 5/8" - 398 FT SP. CUL #180 50' 50' Formin GEL - CA-OL - BY SUN GHT.

ORDER 190 50' 50' Formin GEL - CA-OL - 1" FLAME AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, RECONDITION HOLE (45 VIS) HEAVY MUD BETWEEN ALL PLUGS

NO CIRCULATION PROBLEMS (MUD COND. VIS 44, Weight 12.4, CHLORIDES, 32000

ARBUNLE @ 3368 - ELV. 1929, BATH 806

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 AM Day: 11 Month: MARCH Year: 1985

ACTUAL PLUGGING REPORT ORDERED 190 50' 50' Formin GEL - CA-OL - 1" FLAME + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM, RECONDITIONED HOLE (45 VIS) MUD BETWEEN ALL PLUGS.

1st PLUG @ 3330' / 25' SK CNT, 2nd PLUG @ 820 FT / 25' SK CNT

3rd PLUG @ 570 FT / 80' SK CNT #1 50' 70' GEL, 4th PLUG @ 240 FT / 40' SK CNT

5th PLUG HULL'S-PLUG @ 40 FT / 0' / 10' SK CNT, 10' SK IN RAT HOLE

CIRCULATE WITH JOINT OF PIPE

Remarks: (If additional description is necessary, use BACK of this form.)

NOTED

STATE CORPORATION COMMISSION observe this plugging.

DATE 3-19-85

MAR 18 1985

Signed [Signature] (TECHNICIAN)

INV. NO. 7384

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84