

4-060895

15-009-03354-00-00

20
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

RECEIVED
KANSAS CORP COMM

API Number: 15- - 06-17-48

6-21
1996 JUL -5

SW SW NW /4 SEC. 23 , 16 S, 12 W
2970 feet from S section line
4950 feet from E section line

7-5-96

Operator license# -

Lease Riemann Well # 4

Operator: State of Kansas - Fee Fund

County: Barton

Address: 2301 E. 13th Street - Dist.#4
Hays, Kansas 67601
Mark Casebeer

Well total depth 3378 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 455 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kincaid Well Service License# -

Address: _____

Company to plug at: Hour: 8:00 A.M. Day: 21 Month: June Year: 1996

Plugging proposal received from: District Staff #4

Company: _____ Phone: _____

Were: Order 350 sxs 60/40 posmix - 10% gel and hulls.
Plug with tubing.
Well ~~is~~ flowing gassy oil to surface.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]


Completed: Hour: 11:30 A.M., Day: 21, Month: June, Year: 1996

Actual plugging report: 8 5/8" to 455'. 5 1/2" to 3377'. Perfs at 465' -840' - 1590'. Ran tubing to 2600'. Mixed and pumped 145 sxs cement with 400# hulls with cement to surface. Volume indicate 4 1/2" liner top to bottom. Pulled tubing. Tied onto production casing and pumped 130 sxs cement with 200# hulls. Max. P.S.I. 500#. S.I.P. 200#. Tied onto annulus and pumped 20 sxs cement . Max. P.S.I. 400#. S.I.P. 250#.

Remarks: Allied Cementing - Log-Tech of Kansas - Brackeen - Dakota Dirt.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1929 GL

I did[] / did not[] observe the plugging.


(agent)