

4-23-88

API NUMBER 15-185-22,508-0000

To: 1 120124
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW SW, SEC. 17, T 21 S, R 12 W/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Heaton Well # 9

Operator: National Cooperative Refinery Assoc. County Stafford 118.63
Name & Address Box 6
Great Bend, KS 67530

Well Total Depth 3650 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor: Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 23 Month: 4 Year: 19 88

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 692'
Elevation 1816'

1st plug at 3600' with 50 sx cement, 2nd plug at 690' with 50 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 p.m. Day: 23 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3600' with 50 sx cement,

2nd plug at 690' with 50 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Howco.
(If additional description is necessary, use BACK of this form.)

INVOICED
(old) ~~XXXXXX~~ observe this plugging.

DATE 8-23-88

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 21964

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1988

8-22-88

CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Date April 18, 1988 month day year

API Number 15-185-22,508-0000

License # 5565 National Cooperative Refinery Assoc.

SE SW SW Sec. 17 Twp. 21 S. Rg. 12 East West

Box 6 Great Bend, KS 67530

330 Ft. from South Line of Section 4290 Ft. from East Line of Section

Act Person I. J. Gotsche 316 793-7824

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422 Jacob Partrick Abercrombie Drilling, Inc. Wichita, Kansas

Lease Name Heaton Well # 9 Nearest lease or unit boundary line 330 feet County Stafford

Well Drilled For: Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Ground surface elevation Est. 1864 feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Depth to bottom of fresh water 200' Depth to bottom of usable water 300' 230'

IF OWWO: old well info as follows: 801 Union Center Operator Wichita, KS 67202 Well Name Comp Date Old Total Depth

Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 300' Conductor pipe required None Projected Total Depth 3750 feet Formation Arbuckle

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications. Date 4/8/88 Signature of Operator or Agent I. J. Gotsche Title Dist. Superintendent

For KCC Use: Conductor Pipe Required 10-11-88 feet; Minimum Surface Pipe Required 250 feet per Alt 1 This Authorization Expires 4-11-88 Approved By PCH 4-11-88

EFFICIENCY DATE: 4-16-88 Set 300' of 8 5/8 on 4-16-88

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth, Formation, and Material. Includes entries for Top Arbuckle, Base Anhydrite, Base Surface Pipe, and Rathole to surface.

Log table with columns: Pusher, TD, Surface Pipe, Anhydrite, Starting Time, Completion Time, 1st-4th Plug, Rat Hole, Mouse Hole, Water Well, Cement Company, Technician.

RECEIVED STATE CORPORATION COMMISSION AUG 15 1988 CONSERVATION DIVISION Wichita, Kansas