

To: 1 120762
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-18

API NUMBER 15-185-22,543-0000

NE NE SW, SEC. 14, T. 21 S, R 12 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5140
Operator: Frontier Oil Company
Name & Address 254 S. Maple
Russell, KS 67665

Lease Name Widener Well # 1
County Stafford 117.20
Well Total Depth 3606 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 18 Month: 12 Year: 19 92

Plugging proposal received from Darrell Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 3572' w/150 sx cement, Open hole
1st plug sand back to 3520' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10 a.m. Day: 18 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3520' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.
Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED
I hereby observe this plugging.
DATE 1-6-93
INV. NO. 37118

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1992
Signed Dan Goodrow
(TECHNICIAN)