

15-009-15790-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner D.R.Lauck Oil Company, Inc Address Wichita Kansas  
(Applicant)

Lease (Farm Name) Jarus Well No. 1

well Location C NE NE Sec. 16 Twp. 12 Rge. 12 ~~(E)~~ (W)

County Barton Field Name (if any) \_\_\_\_\_

Total Depth 3333 Oil  Gas  Dry Hole

Was well log filed with application? yes . If not, explain: \_\_\_\_\_

Date and hour plugging is desired to begin July 16 1956

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully and exceptions desired, \_\_\_\_\_

(Use an additional sheet if necessary) \_\_\_\_\_

Name of the person on the lease in charge of well for owner \_\_\_\_\_

H. E. Wolfe Address Ellinwood Kansas

Name of Plugging Contractor R & S Pipe Pulling Co.

Address Ellinwood Kansas

Invoice covering assessment for plugging this well should be sent to \_\_\_\_\_

D.R.Lauck Oil Company, Inc. Address 301 South Broadway Wichita 2 Kans

and payment will be guaranteed by applicant.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 14 1956

John H. Knightley  
Applicant or Acting Agent

Date July 13, 1956

PLUGGING CONSERVATION  
FILE SEC. 16 T. 12 R. 12 W  
BOOK PAGE 80 LINE 7

7-14-56

15-009-1579000-00

D. R. Lauck Oil Company, Inc.

301 South Broadway  
Wichita 2, Kansas

August 8 1956

*Cancelled*

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

Attention: S. S. Greider  
Well Plugging Supervisor

Gentlemen:

This letter is with reference to your letter of July 16th, 1956 granting us the authority to plug the No.1 Jarus well, located in the C NE NE Sec.16-16S-12W Barton County, Kansas, your file No.80-7.

We would like to advise that this lease has been sold to another party and it is not their desire for us to plug this well as was planned.

We would like to withdraw our application to plug the above mentioned well.

Yours very truly,

D. R. LAUCK OIL COMPANY, INC.,

*John H. Knightley*  
John H. Knightley  
Land Department

JHK:G

*Cancel  
&  
file*

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 16 T 12 R 12W  
BOOK PAGE 80 LINE 7



STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA, KANSAS

July 16, 1956

Well No. 1  
Lease Jarus  
Description C&NE NE 16-16-12W  
County Barton  
File No. 80-7

F. R. Lauck Oil Company, Inc.  
301 South Broadway  
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. R. H. Brundage, Box 283, Abington, Kansas.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

By

A handwritten signature in cursive script that reads "S. S. Greider".

S. S. Greider

WELL PLUGGING SUPERVISOR

cc:  
District Plugging Supervisor

15-009-15790-00-00

D. R. BAUCK OIL COMPANY INC. et.al

Jarus #1            Sec.16-16S-12W  
                      Barton County Kansas  
Commenced: Oct.5, 1949

NEc

Completed Oct.22, 1949

Casing: 10" 280' cemented 175 sacks  
          5" 3327'            "        125        "

Shale & shells	40
shale	170
sand	190
shale & shells	325
sand	360
shale & shells	795
Anhydrite	830
red rock	1050
shale & shells	1550
lime & shale	1665
broken lime	1760
lime & shale	1810
lime	1830
lime & shale	1910
lime	2040
shale & lime	2735
lime	3329
Arbuckle	3332

Drill Stem tests:

2908-30 open 15 minutes  
30' mud  
3069-3103 open 10 minutes  
good blow, 90' oil & gas cut mud  
3146-56 open 1 hr  
55' water & mud

Tops - Derrick floor

		Gamma Ray
Heebner	2964	2969
Brown lime	3053	3057
white lime	3069	3073
Conglomerate	none	Gamma Ray
Arbuckle	3327	3331

Standardized:  
derrick floor  
  Top Arbuckle        3327  
  Rotary T.D.        3330  
  Lime                3331  
    800' oil 20 Min.  
lime                3333  
  2000' oil 2 hrs  
swab 500' off bottom  
  1st hr        40 bbls  
  2nd hr        26    "  
  3rd hr        24    "

Total Depth	3333	3336
-------------	------	------

Plug back	12/19/49
T.D.	3260

Perforated	3074-87	48 shots
------------	---------	----------

Completed estimate 100 bbls

PLUGGING  
FILE SEC. 16 T. 16 R. 12W  
BOOK PAGE 90 LINE 9