

15-009-14151-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern & Specter Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name Matilda Jarus Well No. # 1

Location NW SW NE Sec. 16 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3340

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch's Casing Pulling

Address: R. R. # 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 4 P.M. Day 21 Month 1 Year 1965

The Above well was plugged as follows:

15" 80' Old cable tool hole.

Sanded hole back to 3320' & displaced 5 sax cement with dump bailer.

Pulled pipe. Run 2" tubing to 370'; circulated hole with mud. Pulled 4

joints tubing; displaced 55 sax cement thru tubing @ 270' wh/pump truck.

Pulled remaining tubing; set rock bridge @ 30' & displaced 25 sax cement,

cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 1/26/65

INV. NO. 574-w