

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 76-25

LOCATION CNE-NE-NW

SEC. 16 TWP. 16 RGE. 12

Dry Hole _____ Abandoned Oil Well ✓ ^{Cable tool} Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Kultgen

Operator Forbes Casing Pulling Co. Address Box 221, Mt. Bend Kans.

Field _____ County Barton

Total Depth 3361 Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contr. Forbes Casing Pulling Co. Box 221, Mt. Bend Kans.
Casing In hole. 15 1/2" @ 366' No Cem. 10" @ 2119' No Cem.
7" @ 3331' No Cem. P.B. T.D. 3350 1/2 Sanded hole to
3325' dumped 5 sq cem. Pulled 7 and 10" casing.
Mudded hole to 375' dumped 25 sq cem. Shot &
Pulled 15" casing. Mudded hole to 25' Set rock
bridge and run 15 sq cem. to base of cellar

PLUGGING
FILE SEC. 16 T. 16 R. 12 W.
BOOK PAGE 26 LINE 25

Warren H. Horner
District Conservation Agent
Date Dec 10, 1954

12-15-54