

15-009-15787-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sunray DX Oil Company

Complete Address: Box 729, Great Bend, Kansas 67530

Lease Name Kultgen Well No. # 5

Location NW NW Sec. 16 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3352

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Same wh/Dowell Cementing Company

Address: Same License No.

Operation Completed: Hour 4:30 PM Day 14 Month 5 Year 1968

The Above well was plugged as follows:

15 1/2" 335' No cement.

No pipe recovery. Well previously squeezed. Run 2" tubing to 3350' & displaced

50 sax cement, cementing from 3350' to 3150'. Filled hole with mud to 500' & dis-

placed 100 sax cement, cementing to base of cellar. Run 2" tubing between 7" & 15 1/2"

casing to 360'. Circulated hole from 360' to base of cellar with 300 sax cement

with Dowell Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Truman
Well Plugging Supervisor

INVOICED

DATE 5/20/68
INV. NO. 7766-u