

15-009-15789-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Barton

Location: NE SE NW Sec. 16 Twp. 16 Rge. 12W (E) _____ (W) _____

Name of Field: _____ Total Depth: 3337

I have this date completed supervision of plugging of:

Lease Name: Kultgen Well No. 1

Operator's Full Name: Jayhawk Pipe & Supply

Complete Address: 417 State Street, Augusta, Kansas

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 17 Month 2 Year 1962

The above well was plugged as follows:

Sanded hole back to 3330' & dumped 5 sax cement with dump
bailer. Pulled pipe. Mudded hole to 300'. Run 2 1/2" tubing to 300',
& displaced 40 sax cement thru tubing with mud pump. Pulled
tubing. Mudded hole to 25', set rock bridge, & dumped 20 sax
cement, cementing to base of cellar.

Signed: Dan Truman
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED

DATE 3/6/62

INV. NO. 4586-u

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1962
2-21-62
CONSERVATION DIVISION
Wichita, Kansas