

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-009-21896-000 (of this well)

Operator's Full Name Emphasis Oil Operations

Complete Address Box 506, Russell, Kansas 67665

Lease Name Marmie Well No. 1

Location S/2 SW/4 Sec. 16 Twp. 16 Rge. 12 ~~W~~ (W)X

County Barton Total Depth 3395'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:45 AM Day 10 Month 6 Year 1980

The above well was plugged as follows:

Sanded back to 3050' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 5 sx hulls,

25 sx mud gel, plug, and 100 sx cement.

Max. pres 450#. Shut in pres. 150#.

Recovered 2728' of 4 1/2" casing

Plugged back to 3146' Top perforation at 3100'.

3394' of 4 1/2" casing cemented with 125 sx cement.

250' of 8 5/8" surface casing cement circ.

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUN 12 1980

Signed: Duane Rankin  
Well Plugging Supervisor

DATE 6-13-80

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 23532