



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
AIVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Matilda Jarus Well No. # 1

Location: NW SW NE Sec. 16 Twp. 16 Rgs. 12 (E) (W) W

County Barton Total Depth 3340 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

15" 80' Old cable tool hole.

Sanded hole back to 3320' & displaced 5' sax cement with

dump bailer. Pulled pipe. Run 2" tubing to 370'; circulated

hole wh/mud. Pulled 4 joints tubing; displaced 55 sax cement

thru tubing @ 270' wh/pump truck. Pulled remaining tubing;
set rock bridge @ 30' & displaced 25 sax cement, cementing
to base of cellar.

Very truly yours,

David T. ...
Conservation Division Agent