



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 20 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. F. S. Goddard of Sunray DX Oil Company has this date requested permission to plug the following described well:

Mr. F. S. Goddard guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: Box 729, Great Bend, Kansas 67530

Lease Name: Kultgen Well No. # 4

Location: C S/2 N/2NW Sec. 16 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3417 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bob Walters was instructed to plug the well as follows:

15 1/2" 365' No cement.

No pipe recovery. Run 2" tubing to 3417' & displaced 50 sax cement,

cementing from 3417' to 3217". Filled hole with mud to 500' & displaced

100 sax cement, cementing to base of cellar. Circulated hole between

7" & 15 1/2" casing with 300 sax cement with Dowell Cementing Company's

pump truck, cementing from 365' to base of cellar.

Very truly yours,

[Signature]
 Conservation Division Agent