



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. F. S. Goddard of Sunray DX Oil Company has this date requested permission to plug the following described well:

Mr. F. S. Goddard guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: Box 729, Great Bend, Kansas 67530

Lease Name: Kultgen Well No. # 5

Location: NW NW Sec. 16 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3352 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Bob Walters was instructed to plug the well as follows:

15 1/2" 335' . No cement.

No pipe recovery. Well previously squeezed. Run 2" tubing to 3350' &

displaced 50 sax cement, cementing from 3350' to 3150'. Filled hole

with mud to 500' & displaced 100 sax cement, cementing to base of cellar.

Run 2" tubing between 7" & 15 1/2" casing to 360'. Circulated hole from 360' to base pf cellar with 300 sax cement with Dowell Cementing Company's pump truck, cementing to base of cella  
Very truly yours,

*David Truman*  
Conservation Division Agent