

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Company

Complete Address 800 Bitting Building, Wichita, Kansas 67202

Lease Name Hays-Traylor Well No. 1

Location C NE NE Sec. 15 Twp. 23 Rge. (E) (W) 16

County Pawnee Total Depth 4115'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Nicholas Pipe Pulling

Address Box 373, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour 11 A Day 3 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 4115' 8 5/8 csg set at 265' cwc 200 sk.

5 1/2 csg set at 4114' cw 100 sx. & perf. (4026'-4036')

Filled 5 1/2 csg W/sd (4115-4000) dumped 4 sk cem W/dump bailer. (4000-3970)

Cutoff and recovered 2975' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

& pumped 100 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/6/74

INV. NO. 9661-W

Signed: Leo F. Massey
Well Plugging Supervisor