

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

AUG 18 1975

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Voyager Petr. & Sterling Drlg. 15-145-20401-0000

Complete Address Box 129, Sterling, Kansas

Lease Name Schartz Well No. 1

(C NW NW SW)

Location 2310° FSL & 330° FWL Sec. 8 Twp. 23 Rge. (E) (W) 16

County Pawnee Total Depth 4230'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Sterling Drlg., Co.

Address Box 129, Sterling, Ks. License No.       

Operation Completed: Hour 11:45 P Day 15 Month 8 Year 1975

The above well was plugged as follows:

RTD 4230' 8 5/8 csg set 252' cwc 225 sk Cmt. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 400° thru drill pipe. Heavy  
mud to 240° set 25 sk cmt plug thru drill pipe. Heavy mud to 40° set solid bridge  
& 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben Massey  
Well Plugging Supervisor

INVOICED

DATE 8/19/75

INV NO. 1782-W