


KANSAS

Form CP-3
Rev. 6-4-68


STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Robert F. White 15-145-00175-0002

Complete Address 714 Union Center Wichita, Kansas 67202

Lease Name Schartz Well No. 1

Location C N/2 NE NW Sec. 10 Twp. 23 Rge. 16 (X) (W) 2

County Pawnee Total Depth 4070'

Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas 67530 License No. 623

Operation Completed: Hour 12:30 P Day 28 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 4070' 8 5/8 csg set at 210' cwc:

4 1/2 csg set at 4070' cw 125 sk cmt.

4 1/2 csg perf. (3964')

Filled 4 1/2 csg W/sd (3950-4070): Dumped 4 sk cmt W/dump bailer. (3915-3950)

Cutoff and recovered 2225' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug

and pumped 100 sk reg. poz 6% gel. SI pres. 100 lbs. By Allied cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 3/1/72

INV. NO. 5253-11