

15-009-03336-00-00

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
APR 03 1978
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

Operator's Full Name Tenneco Oil Co.
Complete Address 3000 United Founders Blvd. Suite 139, Ciudad Bldg, Okla. City Ok.
Lease Name John Riemann "B" Well No. 2
Location C NW NE SE Sec. 22 Twp. 16 Rge. 12 ~~W~~ (W) X
County Barton Total Depth 3375'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Inc.
Address Box 128 Ellinwood, Kansas 67526 License No. 462
Operation Completed: Hour 11:15 AM Day 31 Month 3 Year 1978
The above well was plugged as follows:

Sanded back to 3050' and 5 sx cement with dump bailer
Squeezed thru 8 5/8" surface casing with 3 sx hulls,
10 sx mud gol, and 100 sx cement.
Max pres 1000#. Shut in pres. 200#.
Top perf. at 3104'. Recovered 524' of 5 1/2" casing.
3369' of 5 1/2" casing cemented with 100 sx cement.
274' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-4-78
INV. NO. 7033-W

Signed: Dwight A. Rankin
Well Plugging Supervisor