

15-009-03337-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 03 1978
CONSERVATION DIVISION
Wichita, Kansas
(Conservation well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Tennece Oil Co.
Complete Address 3000 United Founders Blvd., Suite 139 Ciudad Blag. Okla. City OK.
Lease Name John Riemann "B" Well No. 3
Location C NE NE SE Sec. 22 Twp. 16 Rge. 12 ~~00~~ (W) X
County Barton Total Depth 3370'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated
Plugging Contractor Pipe Pullers, Inc.
Address Box 128 Ellinwood, Kansas 67526 License No. 462
Operation Completed: Hour 2:00 PM Day 31 Month 3 Year 1978

The above well was plugged as follows:

- Sanded back to 3015' and 5 sx cement with dump bailer.
- Squeezed thru 8 5/8" surface casing with 3 sx hulls,
- 25 sx mud gel, 2 sx hulls, and 100 sx cement.
- Max pres. 600#. Shut in pres. 200#. Top perf. at 3108'.
- Recovered 2102' of 5 1/2" casing.
- 3368' of 5 1/2" casing cemented with 100 sx cement.
- 236' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane A. Rankin
Well Plugging Supervisor

DATE 4-4-78
NO. 7034-W