

YD
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name Reimann "C" Well No. # 4

Location SE NE SE Sec. 22 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3362

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch's Gasing Pulling

Address: Rt. #4, Great Bend, Kansas License No. 457

Operation Completed: Hour 5 PM Day 7 Month 9 Year 1963

The Above well was plugged as follows:

8 5/8" 257' Cwc.

Sanded hole back to 3100' & 5 sax cement with dump bailer. Pulled

pipe to 400'; circulated hole with mud; pulled pipe to 300' & displaced

30 sax cement thru pipe with pump truck. Pulled remaining pipe; set

rock bridge @ 40' & displaced 10 sax cement. cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman
Well Plugging Supervisor

DATE 9/9/63

INV. NO. 9911-12