

15-009-03339-00-01

f

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-1-68
RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Tenneco Oil Co.

Complete Address 3000 United Founders Blvd. Suite 139 Ciudad Bldg.
Okla. City, Okla. 73112

Lease Name John Riemann "A" Well No. 1

Location NW NW SE Sec. 22 Twp. 16 Rge. 12 (E) (W) X

County Barton Total Depth 3371'

Abandoned Oil Well X Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers Inc.

Address Box 128 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 8:45 AM Day 14 Month 11 Year 1977

The above well was plugged as follows:

/// Sanded back to 3125' and 5 sx cement with dump bailer.
Squeezed thru 8 5/8" surface casing with 2 sx hulls,
10 sx mud gel, 1 sx hulls, and 100 sx cement.
Max. pres. 550# Shut in Pres. 150#
Plugged back to 3125' Top perf. at 3176
Recovered 607' of 5 1/2" casing.
3357' of 5 1/2" casing cemented with 75 sx cement.
272' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russell Rankin
Well Plugging Supervisor

DATE 11-16-77

INV. NO. 6213-W