

KANSAS

Form CP-3
Rev. 6-1-68
RECEIVED
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

OCT 10 1978

CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-145-26360-0000 (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 West Douglas, Suite 550, Wichita, Kansas 67202

Lease Name Thomas Well No. 1

Location SW NW SW Sec. 19 Twp. 23 Rge. (E) (W) 16

County Pawnee Total Depth 4254'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:30 A Day 9 Month 10 Year 1978

The above well was plugged as follows:

Total Depth 4254' 8 5/8 csg set 308' cwc 225 sk.

4 1/2 csg set 4254' cw 150 sk cem.

4 1/2 csg PBSD 4220' with perf. (4150'-4155') & (4199'-4202')

Squeezed down 4 1/2 csg with 35 sk "Common". top of cem. 3942'.

Cutoff & recovered 2540' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs

hulls, released 8 5/8 plug & mixed & pumped 150 sk 50-50 poz 2% & shutin. FPP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: E. J. Moseley
Well Plugging Supervisor

DATE 10-12-78
INV. NO. 8074-0