

KANSAS

*Y*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 2 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Robert F. White *15-145-20139-0000*  
Complete Address 714 Union Center Wichita, Kansas 67202  
Lease Name Cauble Gas Unit Well No. 1  
Location C SW SW Sec. 22 Twp. 23 Rge. (E) (W) 16  
County Pawnee Total Depth 4080'  
Abandoned Oil Well XX Gas Well XX Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Russ Casing Pulling, Inc.  
Address Box 1082 Great Bend, Kansas 67530 License No. 623  
Operation Completed: Hour 10:15 A Day 1 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 4080' 8 5/8 csg set at 251' cwc

5 1/2 csg set at 4080' cw 125 sk cmt.

5 1/2 csg Perf. (4070-4080)

Filled 5 1/2 csg W/sd (4000-4080) dumped 5 sk cmt W/dump bailer. (3965-4000)

Cutoff and recovered 2300' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug  
and pumped 100 sk 50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 8/3/72  
INV. NO. 6111-W