

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Alpine Drilling Co., Inc. *15-145-00059-0001*

Complete Address 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name Yeager Well No. 1

Location SW SW NE Sec. 22 Twp. 23 Rge. 16 (E) (W) X

County Pawnee Total Depth 41146

Abandoned Oil Well XX Gas Well owuo Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn & Smith Pipe Pulling

Address Box 156 Ellinwood, Kansas License No. 396

Operation Completed: Hour 12:15 P Day 2 Month 12 Year 1970

The above well was plugged as follows:

Total Depth 41146 8 5/8 csg set at 312' cwc

5 1/2 csg set at 41146' cw 100 sk cmt.

5 1/2 csg Perf. (4054)

Filled 5 1/2 csg W/sd (4000-41146) Dumped 5 sk cmt W/dump bailer. (3960-4000)

Recovered 2300' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls, released plug and pumped 100 sk

50-50 poz cmt W/6% gel. Max. pres. 500 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1-5-71

INV. NO. 3146-W