

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-145-00428-0001

Operator's Full Name Robert F. White

Complete Address: 714 Union Center Wichita, Kansas 67202

Lease Name Curtis Well No. 1

Location C SE NE NE Sec. 25 Twp. 23 Rge. 16 (E) (W) X

County Pawnee Total Depth 4291

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 7:30P Day 2 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 4291' 10 3/4 csg set at 613' cwc

5 1/2 csg set at 4291' cw 200 sc cement.

5 1/2 csg PBTD 4263' with perf. (4082-92)

Filled with sand to 4000' and dumped 5 sc cement with dump bailer.

Recov. 2768' of 5 1/2 csg.

Pumped thru 10 3/4 swage with 20 sc gel W/5 sc hulls, plug and 125 sc cement.

Max. Pres. 500 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Prof. Massey  
Well Plugging Supervisor

INVOICED

DATE 7/9/68  
INV. NO. 8052-W