

15.159.20279.0000

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Northridge Oil Company

Complete Address Box 18271, 536 Gilpin Street, Denver, Colorado 80218

Lease Name Walsten "C" Well No. 1

Location C NW NW Sec. 8 Twp. 21 Rge. 6 (E)      (W) X

County Rice Total Depth 3510'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Dunbar Drilling Company

Address 5252 North Broadway, Wichita, Kansas License No. 709

Operation Completed: Hour 3 PM Day 5 Month February Year 1974

The above well was plugged as follows:

Hole filled with sand to 3450' and cemented with 5 sacks cement. Hole filled with  
mud to 210'. Rock bridge set from 210' to 200' and hole cemented with 25 sacks  
cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole  
cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *Arthur J. Leonard*  
Well Plugging Supervisor

INVOICED  
DATE 2/18/74  
INV. NO. 8580-W