

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mr. Hazen of Hazen Oil Company has this

date requested permission to plug the following described well:

Mr. Hazen Oil Company guarantees payment of the plugging fee.

Operator's full Name: Hazen Oil Company

Complete Address: 404 East 6th., Ellinwood, Kansas 67526

Lease Name: Morgan "B" Well No. # 7

Location: SW SE NE Sec. 22 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3378 Oil Well XX

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Darrell Kelso was instructed to plug the well as follows:

8 5/8" csg. ~~XXX~~ 300' Cwc. Perf. 3113'

Sanded hole back to 3100' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, released plug,
& displaced 100 sax cement with Allied Cementing Company's pump truck,
cementing from 320' to base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent