

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 9 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Morton Specter of Morgenstern & Specter has this

date requested permission to plug the following described well:

Mr. Morton Specter guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Specter, Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name: Riemann "C" Well No. # 4

Location: SE NE SE Sec. 22 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3362 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Lynch was instructed to plug the well as follows:

8 5/8" 257' Cwc.

Sanded hole back to 3100' & 5 sax cement with dump
bailer. Pulled pipe to 400'; circulated hole with mud;
pulled pipe to 300' & displaced 30 sax cement thru pipe
with pump truck. Pulled remaining pipe; set rock bridge
@ 40' & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don. Tripp
 Conservation Division Agent