



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. E. T. Drube of M. J. Bove has this

date requested permission to plug the following described well:

Mr. E. T. Drube guarantees payment of the plugging fee.

Operator's full Name: M. J. Bove

Complete Address: 754 E. Wichita, Russell, Kansas

Lease Name: Reiman Well No. # 4

Location: NW SW SW Sec. 23 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3366 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bob Barnes was instructed to plug the well as follows:

8 5/8" 158' Cwc.

Set bottom plug @ 3100' & dumped 5 sax cement with dump
bailer. Pulled pipe to 450'; circulated hole with mud; dis-
placed 25 sax cement thru pipe @ 300'. Pulled pipe to 155';

displaced 20 sax cement with Sun Cementing Company's pump truck.
Pulled remaining pipe; set rock bridge & displaced 10 sax
cement, cementing to base of cellar.

Don Truman
Conservation Division Agent