

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 13 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Nathan Meltzer of Great Bend Pipe & Supply has this date requested permission to plug the following described well:

Mr. Nathan Meltzer guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas

Lease Name: Reiman Well No. # 2

Location: NW Sec. 23 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3413 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mike Wassinger was instructed to plug the well as follows:

8 5/8" 512' Cwc.

Sanded hole back to 3360' & dumped 4 sax cement with
dump bailer. Pulled pipe. Bailed hole down to 350'; set
rock bridge; displaced 30 sax cement. Mud to 40'; set
rock bridge; displaced 10 sax cement, cementing to base

of cellar.

Very truly yours,

Don Truman
 Well Plugging Supervisor