

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 18 1967

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Doyle Rand of Harms Petroleum Company has this
 date requested permission to plug the following described well:

Mr. Pipe Pullers, Inc. guarantees payment of the plugging fee.

Operator's full Name: Harms Petroleum Company

Complete Address: Box 488, Great Bend, Kansas

Lease Name: Hofmeister Well No. # 1

Location: NE SW SE Sec. 23 Twp. 16 Rge. 12 (E)(W) W

County Barton Total Depth 3343 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. C. B. Bradley was instructed to plug the well as follows:

8 5/8" 184' Cwc. 5 1/2" 3339' Plug @ 3210' Perf. 2925'.

Set bottom plug @ 2900' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 290', set 10' rock bridge, & displaced

5 yds. ready-mix cement, cementing from 280' to base of cellar.

Very truly yours,

Xone L. L. L.
 Conservation Division Agent