



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

March 14, 1963.

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Darrell Kalso of Knight Caseing Pulling Co has this date requested permission to plug the following described well:

Mr. Darrell Kalso guarantees payment of the plugging fee.

Operator's full Name: Great Bend Pipe Pulling Co.

Complete Address: Drawer B Great Bend, Kansas.

Lease Name: Heaton #5 Well No. #5

Location: SW-SE-SW Sec. 17 Twp. 21 Rge. 12 (E) (W)

County Stafford Total Depth 3588' Abandoned Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Darrell Kalso was instructed to plug the well as follows:

3536' of 5 1/2" long string. Hole sanded to 3530' & 5 sacks cement.
2870' pipe pulled. 329' of surface pipe circulated with
cement. Hole filled to 200' with mud, 10' rock bridge & 20
sacks cement. Hole filled to 40' with mud, 10' rock bridge
& 10 sacks cement to base of cellar.

Very truly yours,

Thompson Gustus
Conservation Division Agent